

Phase One

Layout, Lot Preparation & Permits

Using the layout drawing of your backyard, marking off your pool is the first step. Any lot preparation will be completed at this time.

Preparations, such as fence removal, may also be necessary to provide access for the heavy equipment that will be in your backyard. Memphis Pool will apply for all the government permits to insure your pool is built in full compliance of building codes.

Excavation

Pool excavation requires heavy machinery and a dump truck to remove any dirt not needed around the pool. It is possible your landscaping around the pool and access area could be heavily damaged, as pool construction is an untidy process.

Unusual conditions such as rock, collapsible soil, or high water table may occur. In such instances, there will be a need to discuss the best option. Most options are likely to add cost to the job.

Steel & Pre-Plumb

A crew will set and tie a network of steel reinforcing bars to conform to the shape and contour of your pool. Plumbing and lighting fixtures will be carefully positioned into place. An inspection by the local electrical code inspector will then follow.

Gunite Application

Cement and sand loads will arrive prior to applying the gunite. Heavy machinery and large trucks will be on the grounds, since Guniting requires large equipment. As exciting as the process is, it is noisy and will stir up dust.

Our skilled craftsmen will pneumatically apply the gunite over the steel to form a single-piece gunite shell that will provide the structural strength for your pool...a structure that will endure a lifetime! The crew will trim out the final shape of the pool and cut-in such features as steps and benches.



Building the world's finest pools

