

Phase Two

Tile & Coping

Our tile installers will set your selected ceramic tile around the water line perimeter of the pool. Your selection of top border coping will also be installed, giving your pool an attractive, safe, and durable edge.



Pool Plumbing

After trenches for the circulation piping system are dug, our crew will install the multiple plumbing lines that run between the pool and the filter system. The plumbing system will be pressure tested. Although we attempt to have all underground lines located, please be aware that the digging for your plumbing may cut cable, phone, or existing sprinkler lines.



Decking Form Boards

Now you can more realistically see how your pool will look in your backyard. It's time to set the forming boards for your concrete decking. Many of our agreements allow for you to alter the decking shape and size at this time. We can meet with you, revise the plan, and advise you of additional costs.



Electrical Rough-in, Bonding & Inspection

An electrician will install the electrical wiring for the underwater lighting and provide a safety bonding around the pool. This must be inspected by a government electrical inspector prior to pouring any concrete decking.



Concrete Decking

When the concrete is poured, adequate expansion joints will be installed, and the concrete deck will be equipped with a fibermesh reinforced additive to help minimize cracking and chipping of the concrete as it ages.

