

# Phase Three



## Install Filtration Equipment

Your pump and filter system will be set in place and connected to the plumbing. Other equipment included in your contract, such as an automatic chlorinator, automatic cleaner, and heater are installed at this time.

## Install Final Electrical for Pump & Lighting

The final electrical connections and switches for your pump(s), heater, and lighting are now installed.

## Remove Forming Boards & Grade Yard

Deck forming boards are removed and grading is done to "level" the area around the pool decking. If you are working with a landscape contractor, now is the time for them to get involved for final grading, sodding, etc.

## Apply Interior Finish & Fill with Water

It's time to cover the gunite with the interior surface you have selected (Plaster, Pebble Tec, or other options). Crews will mix up, hand trowel and finish the surface. Step and bench accent tile (except for Pebble Tec finishes) will be installed as agreed. When completed, we'll begin filling your pool with water.



Building the  
world's finest pools

